Approximate Quantity.

Items of work.	Quantity.	Remarks.
Earth work excavation and filling basement ..	449 cyd.	
Concrete foundation	5,164 cft.	
Stone in chunam foundation and basement ..	7,689 cft.	
Burnt brick in chunam	17,600 cft.	
Arch work	1,889 cft.	
Slab stone 6″ thick	814 sft.	
Chunam plastering	280·88 sqr.	
Pointing	10·14 sqr.	
White and color washing	291·02 sqr.	
Cornice work	648 rit.	
Teak wood work	769·25 cft.	
Roofing with Mangalore tiles with reepers ..	71·82 sqr.	All materials will be supplied by Government on the spot and the contractor will be paid only for fixing.
Ornamental ridge tiles..	227 each.	
Sloping or Bengal terrace including plastering ..	10·39 sqr.	
Teak wood doors	948 sft.	Rate per cubic feet of frame and square feet of shutters glazed and panelled to be quoted, iron bars price per maund to be quoted. All panelled and glazed shutters will have to be 1½″ thick.
Teak wood windows	1,877 sft.	
Wood oiling	89·74 sqr.	
Painting doors and windows	29·19 sqr.	
Concrete flooring including plastering ..	2,003 cft.	
Slabs stone flooring including pointing with asphalet.	7·85 sqr.	
Bamboo matting with outer rind	42·12 sqr.	
Teak wood finials at ends of roof	No. 6	
Zinc sheet	256 sft.	
Clearing site lump sum ..	Rs. 25.	

C. T. DALAL, *Exec. Engr.*

MYSORE DIVISION.

The 25th November 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 20th December 1897, for restoring and improving the Homma tank, Registered No. 35 of Chamrajnagar taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and improving the Homma tank, Registered No. 36 of Chamrajnagar taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

	Items.	*Per.*	*Quantity.*	*Rate.*
Bund—				
	Earth work	C. yd.	45,003	
	Turfing	Sqr.	27,881	
	Rough stone revetment	C. yd.	1,340	
	Fixing new grade stones with lead and edge stones ..	No.	72	
	Gauge stone	,,	1	
	Register number stone	,,	1	
	B. M. stones	,,	2	
	Clearing jungle	Lump sum.		
Waste weir—				
	Extending weir	R. ft.	200	
Sluices—				
	Examining and repairing New sluices	Lump sum.		
Distribution—				
	Constructing an acqueduct	,,		
Supply—				
	Improving feeder channel	,,		